

30-12-19W P1

DONALD J. MELLAND * PETROLEUM GEOLOGIST

401 Peoples Bank Building * Post Office Box 783 * McPherson, Kansas 67460
Office (316) 241-7907 * Residence (316) 241-4582

SEP 2 9 1985

G E O L O G I C A L R E P O R T

State Geological Survey
WICHITA BRANCH

E C C O

Raymond Ambrister # 2 ✓

S/2 S/2 SE, Sec. 30-12-19W 300' from S. Line

Field: Weisner East 1340' from E. Line

Ellis County, Kansas

November 22, 1982

Elevation: 2158 KB

Comm: 11/10/82; Comp: 11/19/82

Casing: 8-5/8" @ 263'/200sx:

17# 5-1/2" @ 3860'/140sx.

API # 15-051-23236

License # 5210

FORMATION TOPS

	<u>Sample</u>	<u>Electric Log</u>
9/9-11/85 Dakota Breakin	810.88' From Surface	(Per marks on Tubing)
Anhydrite		1501 (-657)
Topeka	3199 (-1041)	3197 (-1039)
Heebner	3432 (-1274)	3432 (-1274)
Toronto	3452 (-1294)	3453 (-1295)
Lansing	3472 (-1314)	3472 (-1314)
BKC	3712 (-1554)	3713 (-1555)
Marmaton	3766 (-1608)	3766 (-1608)
Conglomerate	3812 (-1654)	3812 (-1654)
RTD	3861 (-1703)	3860 (-1702)

Cores: None

Drill Stem Tests: Two tests were taken in the Lansing by Halliburton Services, job logs attached.

Electrical Logs: A Gamma-Guard Sidewall Neutron log was run at total depth.

Detector: None

Measurements: Were taken from Kelly bushing, 5 feet above ground level. Drill pipe was strapped at 3336 feet - no corrections were made. The following depths have been taken from electric logs measurements.

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1985

CONSERVATION DIVISION
Wichita, Kansas