

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY MARTIN & KELLER

SEC. 31 T. 12 R. 19W
LOC. NE SE NE

FARM Schoenthaler NO. 2

COUNTY Ellis

TOTAL DEPTH 3711'

COMM. 12-20-67

COMP. 12-30-67

SHOT OR TREATED

CONTRACTOR Leben Drilling

ISSUED 3-9-68

KANSAS

CASING

20	10	
15	8	5/8" 208' cem w/ 150 sx
12	6	
13	5	

ELEVATION 2146' KB

PRODUCTION 123 BOPD/TR W
Lans 3451-3655

FIGURES INDICATE BOTTOM OF FORMATIONS

0	35	Clay, Post Rock	TOPS: LOG
35	210	Gravel, Shale	Anhydrite (s) 1499
210	850	Blue Shale	Topeka 3178
850	1405	Sand, Shale	Heebner 3415
1405	1499	Shale	Toronto 3430
1499	1540	Anhydrite	Lansing 3457
1540	2050	Shale, Shells	Base Kansas
2050	2550	Lime, Shale	City 3500
2550	2640	Lime LTD	3710
2640	3060	Shale, Lime Streak	TD 3711
3060	3130	Lime, Shale	
3130	3418	Lime	
3418	3420	Heebner	
3420	3457	Lime	
3457	3458	Lansing Lime	
3458	3710	Lime	
	<u>3710</u>	<u>RTD - Set 4 1/2" Casing</u>	
	3711	LTD	

8 5/8" used 28# surface casing set @ 208' cemented with 150 sacks
Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Schoenthaler #2 Well, located NE SE NE of Section 31, Township 12 South, Range 19 West, Ellis County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
Leslie Kite

STATE OF KANSAS)
COUNTY OF BARTON) SS