

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **MARTIN & KELLER**

SEC. 32 T. 12 R. 19W

FARM **Bahl**

NO. **1**

LOC. SE NW SW

TOTAL DEPTH **3853'**

COUNTY

Ellis
KANSAS


COMM. **4-14-67**

COMP. **4-24-67**

SHOT OR TREATED

CONTRACTOR **Leben Drlg., Inc.**

ISSUED **7-22-67**



CASING

20	10	
15	8 5/8	239' w/165 sx cem.
12	6	
13	8 4 1/2	3852'

ELEVATION **2135' K.B.**

PRODUCTION **104 BOPD & 20% W.-Lans 3622-28 Gr. 39.2**

FIGURES INDICATE BOTTOM OF FORMATIONS

0	45	Post Rock
45	239	Sand, Shale
239	800	Shale
800	940	Sand, Shale
940	1175	Sand
1175	1480	Redbed
1480	1528	Anhydrite
1528	1680	Shale
1680	2023	Shale, Lime
2023	2285	Lime, Shale
2285	2735	Lime
2735	2945	Shale, Lime
2945	3100	Lime, Shale
3100	3425	Lime
3425	3460	Lime, Chert
3460	3820	Lime
3820	3852	Cherty Lime
	<u>3852</u>	<u>RTD - Sol 4 1/2" Casing</u>
	3853	Cherty lime T.D.

RECEIVED
 STATE GEOLOGICAL SURVEY
 APR 27 1967
 OBSERVATION DIVISION
 WICHITA, KANSAS

8 5/8" 20# new surface casing set @ 239' cemented with 165 sacks of Common, 2% cc

TOPS: SCOUT	
Anhydrite	1480
Topeka	3167
Heebner	3401
Toronto	3424
Lansing	3446
B/Kansas City	3692
Marmaton	3784
Arbuckle	3824