


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- HOUSTON-SIMPSON & CHANDLER
 Farm- Huber No. 1

SEC. 32 T. 12 R. 20W
 NE NW SE

Total Depth. 3875'
 Comm. 3-25-58 Comp. 4-5-58
 Shot or Treated.
 Contractor. Sierra Petr.
 Issued. 5-10-58

County Ellis
 KANSAS



CASING:
 8 5/8" 346' cem w/175 sx.

Elevation. 2176' KB

Production. Dry

Figures Indicate Bottom of Formations.

post rock	60
sand	130
shale & shells	346
shale & shells & sand	750
shale, shells, pyrite	1050 ✓
sand & shale	1245
shale & red bed	1530
Anhydrite	1565
shale & shells	1900
shale & salt	2065
shale & lime	3450
lime	3691
lime & shale	3735
lime & chert	3804
Conglomerate chert	3844
Arbuckle	3875
Total Depth	

TOPS:	
Anhydrite	1530
Heebner	3441
Toronto	3462
Lansing-Kansas City	3472
Base Kansas City	3728
Conglomerate (scout)	3815
Arbuckle	3845