


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas

Company- **AMERICAN PETRO-FINA**  
 Farm- Huber "A" No. 2

SEC. 32 T. 12 R. 20W  
 NW NE SW

County Ellis  
 KANSAS

Total Depth. 3848'  
 Comm. 5-2-60 Comp. 5-12-60  
 Shot or Treated.  
 Contractor. Sierra Petro. Co., Inc.  
 Issued. 7-30-60



Elevation. 2191' KB

Production. 58 BOPD

**CASING:**

8 5/8" 363' w/225 sx cem.  
 5 1/2" 3845' w/400 sx cem.

Figures Indicate Bottom of Formations.

top soil, post rock	40
rock-few sand stks	75
shale	363
shale, shells	900
shale	1290
lime, shells	1340
shale, shells	1505
shale	1520
lime, anhydrite	1570
shale, shells	2055
salt, shale, shells	2095
lime, shale	2360
lime	2390
lime, shale	3494
lime	3539
lime, shale	3643
lime	3765
lime, shale	3844
lime	3848
Total Depth	

**TOPS:**

Heebner	3439
Toronto	3460
Lansing, Kansas City	3477
Brown lime	3730
Arbuckle	3844

**TOPS: SCOUT**

Marmaton lime	3768
Conglomerate shale	3797
Conglomerate chert	3816