

RECEIVED

NOV 07 2003

CONFIDENTIAL

Wendling #4 KCC WICHITA

3045' FNL & 2340' FEL or apprx NW NW SE. Sec 19-12s-20w. Ellis County KS.
Spud 06-23-77.

Elevation - 2263' GL, 2268' KB.

8 5/8" 24# Csg @ 220' w/ 150 sx.

Topeka Top @ 3291' (-1023').

DST #1 @ 3308' - 3330' (Upper Topeka) recovered 30' VSOCWM, 180' MW w/ oil spots, 120' W, 1103# - 1079#.

DST #2 @ 3412' - 3508' (Lower Topeka) recovered 72' SOCM, 62' OCM, 310' HOCM,

62' OCWM, 1273# - 1249#.

LKC Top @ 3558' (-1290').

DST #3 @ 3575' - 3608' (LKC Top - 35') recovered 186' MW w/ oil spots, 425# - 400#.

DST #4 @ 3682' - 3756' (LKC 140' - 200') recovered 30' mud, 62' OSM, 62' SOCM, 62' OCM, 62' HOCM, 124' MO, 238' SMCO, 10' OW, 512# - 487#.

Marmaton Top @ 3854' (-1586').

Erosional Arbuckle Top @ 3935' (-1667').

Clean Arbuckle Top @ 3940' (-1672').

DST #5 @ 3892' - 3942' (Arbuckle) recovered 65' mud w/ oil specks, 838# - 789#.
RTD - 3942'.

LTD - 3943'.

5 1/2" 14# Csg @ 3942' w/ 175 sx. Pozmix on 07-02-77. (ScotchCoat csg top 1616').

ORIGINAL

Handwritten signature

KCC

NOV 07 2003

CONFIDENTIAL

Release
DEC 10 2003
From
Confidential