

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


COPY

Company- WHITE EAGLE OIL COMPANY  
Farm- Huber No. 1

SEC. 19 T. 12 R. 20W  
SW SW SE

Total Depth. 3940'  
Comm. 7-9-57 Comp. 7-21-57  
Shot or Treated.  
Contractor. Glenn W. Peel  
Issued. 11-2 -57

County Ellis  
KANSAS



CASING:  
8 5/8" 374' cem

Elevation. 2228 RB

Production. Dry

Figures indicate Bottom of Formations.

Surface clay	374
Shale and shells	1650
Shale	1965
Shale & shells	2200
Shale & lime	2540
Lime	2610
Lime & shale	2905
Lime	2990
Lime & shale	3350
Lime	3805
Lime and chert	3838
Lime	3940
Total Depth	

TOPS:

Topeka Lime	3248
Heebner Shale	3476
Toronto Lime	3497
Lansing Kansas City	3514
Conglomerate	3810
Arbuckle	3896

DST #1 - Lansing 3606-3620' - Tool open 1 hr. Good blow throughout. Rec. 170' heavy oil and gas - cut mud and 10' salt water. Pressures: IBHFP 0#; SIBHP 920# (20 min.)

DST #2 - Lansing 3714-3726 - Tool open 1 hr. Very good blow immediately, decreasing to weak blow in 45 min. Rec. 2650' salt water. Pressures: IFP 400#; FFP 1243#; ISIBHP 1327# (20 min.); FSIBHP 1270# (20 min.)

DST #3 - Arbuckle 3897-3903' - tool open 30 min. Weak blow for 2 min., intermittent blow for 4 min. and died. Rec. 8' mud with specks of live oil. Pressures: BHFP 0#; SIBHP 734# (15 min.), rising sharply. HP 2183#.

DST #4 - Arbuckle 3898-3912' - Tool open 40 min. Weak blow for 1 min. & died. Intermittent blow for 10 mins. & died. Rec.: 10' slightly OCM; 15' HOCM. Pressures: BHFP 0#; SIBHP 1133# (20 min.); HP 2200#.