

K.G.S. LIBRARY

WELL LOG

K.G.S. LIBRARY

SECTION FOR LOCATION INFORMATION

COMPANY A. Scott Ritchie

SEC. 30 T. 12S R. 20W  
LOC. SE SW NE


FARM WIESNER "B" NO. 2

RIG. NO. 15

COUNTY Ellis  
KANSAS

TOTAL DEPTH 3900'

COMM. 6-1-79 COMP. 6-8-79



CONTRACTOR Murfin Drilling Company

CASING  
20 10  
15 8-5/8" w/150 sx.  
12 6  
13 5

ELEVATION GL: 2194'  
KB: 2199'

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS


- 175' Surface Clay & Shale
- 1045' Shale
- 1265' Sand
- 1340' Shale (Red Bed)
- 1553' Shale
- 1600' ANHYDRITE
- 2810' Shale
- 3140' Shale & Lime
- 3454' Lime & Shale
- 3750' Lime
- 3835' Lime & Chert
- 3900' Lime RTD

A. SCOTT RITCHIE  
125 N. MARKET  
WICHITA, KS 67202 #2 WIESNER "B" 30-12-20W SE SW NE

CONTR MURFIN DRILG CO. CTY ELLIS

GEOL FIELD ELLIS EXT (1/8 N)

E 2199 KB CM 5/31/79 CARD ISSUED 6/23/79 IP D&A/CONG 6/7/79



API 15-051-21,701

SMP	TOPS	DEPTH	DATUM
ANH		1553	+ 646
B ANH		1600	+ 599
TOP		3221	-1022
HEEB		3454	-1255
TOR		3475	-1276
LANS		3492	-1293
BKC		3741	-1542
MARM		3790	-1591
CONG		3838	-1639
RTD		3900	-1701

8-5/8" 175/150sx

NO LOG

DST (1) 3240-3264/30-30-30-30, REC 120' O SPKD M, SIP 1092-1019#, FP 115-115/115-115#

DST (2) 3343-3454/30-30-30-30, REC 180' M, SIP 1196-1174#, FP 138-161/184-207#

DST (3) 3460-3512/30-30-30-30, REC 10' M, SIP 138-92#, FP 69-69/69-69#

INDEPENDENT OIL & GAS SERVICE WICHITA, KANSAS