

KANSAS DRILLERS LOG

API No. 15

051

County

Number

Operator

Robinowitz Cil Company

Address

6650 South Lewis Tulsa, Oklahoma 74136

Well No.

#5

Lease Name

Wiesner

Footage Location

990

feet from (S) line

990

feet from (E) line

Principal Contractor

Emphasis Oil Oper

Geologist

Lewis O. Chubb

Spud Date

Nov 4, 1977

Total Depth

3890

P.B.T.D.

3850

Date Completed

Dec 10, 1977

Oil Purchaser


S. 30 T. 12 R. 20 W

Loc. NW SE SW

County Ellis

640 Acres

N



Locate well correctly

Elev.: Gr. 2199

DF 2201 KB 2204

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Water Socket	12	8 5/8		239	Rig	150	3% gel
Prod String	7 7/8	5 1/2	15.5#	3889'	Rig	150	10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		3876-86
TUBING RECORD					
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
acid w/ 400 gal 15% HCl	3876-86

ROBINOWITZ OIL CO.

6650 SO. LEWIS

TULSA, OK.

CONTR EMPHASIS OIL OPERATIONS CTY ELLIS

GEOL FIELD ELLIS

E 2204 KB CM 11/4/77 CARD ISSUED 4/20/78 IP SWDW ARB 3866-90

API 15-051-21,395

LOG	TOPS	DEPTH	DATUM
CED HILLS	1060	+1144	
ANH	1565	+ 639	
TOP	3216	-1012	
HEEB	3442	-1238	
TOR	3463	-1259	
LKC	3479	-1275	
RKC	3731	-1527	
MARM	3782	-1578	
PENN CONG	3825	-1621	
ARB	3868	-1664	
RTD	3888	-1684	
DDTD	3890	-1686	

8-5/8" 239, 5 1/2" 3886

DST (1) 3450-3500/30-30-30-30, 70'

SOCM, SIP 819-797#, FP 45-57#, 57-68#

DST (2) 3504-70/30-30-30-30, 165' SWCM

SIP 505-493#, FP 69-92#, 103-115#

BHT 107°


DST (3) 3874-90/15-30-15-30, 20'M

SIP 1011-853#, FP 22-22#, 22-22#

BHT 120°

MICT - CO TO 3888', DD TO 3890'

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Operator <u>Robinsonitz Oil Co</u>		DRY HOLE, SWDW, ETC.: <u>SWD.</u>	
Well No. <u>5</u>	Lease Name <u>WIESNER</u>		
S <u>30</u> T <u>12</u> R <u>20</u> W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
			DEPTH
Torrey	3216	3238	Radiation
Hebner	3442	3463	Gehrlog
Toronto	3463	3479	
Lansing A	3479	3514	
" B	3514	3556	
" EFF	3556	3574	
" G	3574	3670	
" J	3670	3685	
Gas Lansing	3731		
Marmaton chert	3782	3825	
	3825	3868	
Conglomerate	3868		
arectile	3888		
TD			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature		
	<u>Petroleum Engineer</u> Title		
	<u>Jan 5, 1979</u> Date		