1-13-22 api 1117182 KCC

TYPE

SIDE ONE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

State Geological Survey
WICHITA BRANCH

CONFIDENTIAL

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 6177 EXPIRATION DATE August, 1983

OPERATOR Foxfire Exploration, Inc. API NO. 15-195-21,095

ADDRESS 10403 West Colfax Avenue - Suite 610 COUNTY Trego

Lakewood, CO. 80215 FIELD

** CONTACT PERSON D. C. Marchant PROD. FORMATION NA

PHONE (303) 234-1352

PURCHASER NA LEASE Peterson

ADDRESS WELL NO. 1

WELL LOCATION NE NE SE

DRILLING CONTRACTOR Red Tiger Drilling Company

990 Ft. from North Line and

ADDRESS 1720 KSB & T Bldg.

330 Ft. from East Line of

Wichita, KS 67202

the SE (Qtr.) SEC 1 TWP 12S RGE 22W.

PLUGGING CONTRACTOR Allied Cementing Company

WELL PLAT (Office Use Only)

ADDRESS Box 31, 332 W. Wichita


Russell, KS 67665

KCC ✓

KGS

SWD/REP

PLG.



TOTAL DEPTH 4100' PBTD

SPUD DATE 10-26-82 DATE COMPLETED 11-7-82

ELEV: GR 2360 DF 2362 KB 2364

DRILLED WITH ~~(CABLE)~~ (ROTARY) (~~AIR~~) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE .

Amount of surface pipe set and cemented 326.29' DV Tool Used? .

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, (Dry), Disposal, Injection, Temporarily Abandoned, OWWO. Other .

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

RECEIVED
STATE CORPORATION COMMISSION

DEC 6 1982

CONSERVATION DIVISION
Wichita, Kansas

A F F I D A V I T

D C MARCHANT, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

D C Marchant
(Name)

RD

104168

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR Foxfire Exploration LEASE Peterson #1 SEC. NE TWP. NE RGE. SE
1 125 22W

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Clay	0	337	Anhydrite Top	1806
Shale	337	770	Anhydrite Base	1855
Shale & Sand Sts	770	1306	Topeka	3413
Sand	1306	1524	Heebner	3631
Shale	1524	1820	Toronto	3650
Anhydrite	1820	1861	Lansing	3667
Shale	1861	2609	KS City Base	3906
Lime & Shale Sts	2609	2702	Marmaton	3978
Shale & Lime	2702	2805	RW Arbuckle	4074
Lime & Shale	2805	3046		
Lime	3046	4088		
Arbuckle	4088	4100		
RTD		4100		

DST #1 - 3667-3720, 30-30-30-30, Rec. 40' mud, FP 58-58#, SIP SIP 1046-966#

DST #2 - 3753-68, 30-60-30-60, Rec. 635' MW with trace of oil, FP 93-336#, SIP 772-726#

DST #3 - 3847-59, 30-30-30-30, Rec. 10' mud, FP 35-35#, SIP 1184-1161#

DST #4 - 3987-4003, 30-30-30-30, Rec 10' WM, FP 35-35#, SIP 139-81#

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or ~~(Used)~~

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12¼"	8-5/8"	20#	334'	60-40 Poz	200 sx	2% Gel., 3% C.C.

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

TUBING RECORD

Size	Setting depth	Packer set at

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval