

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Colorado Oil Company

SEC. 26 T. 12 R. 22W
 LOC. NW SW SE

FARM SCHOENTHALER NO. 13

RIG. NO. 8

TOTAL DEPTH 3960'

COMM. 10-14-67

COMP. 10-25-67


SHOT OR TREATED

CONTRACTOR MURFIN DRILLING COMPANY

ISSUED 1-20-68



COUNTY Trego - Kansas
 KANSAS



CASING

20 10 3/4" @ 252' w/210 SX
 15 8
 12 6
 13 5
 7" @ 3945' w/175 SX

ELEVATION 2311' KB

PRODUCTION Oil P 180 BOPD, NW
 ARB 3954-60

FIGURES INDICATE BOTTOM OF FORMATIONS

55 Clay- Sand
 258 Shale
 540 Sand & Shale
 1020 Sand
 1230 Shale
 1350 Sand
 1580 Shale Red Bed
 1605 Sand
 1704 Sand Red Bed
 1750 Anhydrite
 2480 Shale
 2840 Lime & Shale
 3190 Shale-Lime
 3230 Lime
 3390 Top Lime
 3455 Lime-Shale
 3475 Lime & Shale Sks
 3945 Lime
 3960 Arbuckle

TOPS: SCOUT
 Anhydrite 1700
 Topeka 3288
 Heebner 3529
 Toronto 3546
 Lansing 3561
 B/Kansas City 3799
 Pawnee 3886
 Conglomerate 3930
 Arbuckle 3949

State of KANSAS }
 County of SEDGWICK } ss:

I, James R. Daniels of the MURFIN DRILLING Company

upon oath state that the above and foregoing is a true and correct copy of the log of the SCHOENTHALER #13 well.