

✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **TEXACO, INC.**
Farm- **Geroge Bittel** No. **12**

SEC. **27** T. **12** R. **22W**
 NE SE SE

Total Depth. **4048'**
Comm. **4-15-65** Comp. **4-27-65**
Shot or Treated.
Contractor. **Murfin Drlg. Co.**
Issued. **9-18-65**

County **Trego** **KANSAS**



CASING:

9 5/8" 322' w/165 sx cem.
7" 4023' w/150 sx cem.

Elevation. **2358' Gr**

Production. **Pmp 154 BOPD & 5 BWPD**

Figures Indicate Bottom of Formations.

surface soil, clay	30
sand	50
Post Rock	75
sand, shale	280
shale	760
shale w/sand strks	1250
sand	1340
shale	1746
Anhydrite	1798
shale	1805
shale, shells	2030
shale	2354
lime, shale	2512
shale w/lime strks	2565
lime, shale	3460
lime	3604
lime, shale	3635
lime	3816
lime, shale	3836
lime	3955
lime, shale	3980
lime	4015
Arbuckle	4048 RTD
Total Depth	

TOPS: SCOUT

Heebner	3582
Lansing	3616
Lansing "F" Zn.	3691
Lansing "G" ?	3712
" " " "	3758
" " " "	3774
" " " "	3798
B/Kansas City	3854
Arbuckle	4020

Ran Radiation-Guard & Acoustic
Velocity logs.