


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **THE TEXAS COMPANY**
 Farm- **Kellogg-Lynn No. 2**
Ogallah Unit was Lynn 2

SEC. 25 T. 12 R. 22W
SE SW SE

Total Depth. 4005
Comm. 6-22-52 Comp. 7-9-52
Shot or Treated.
Contractor. Powell Drlg.
Issued. 8-9-52

County Trego KANSAS



0320(2nd)
Elevation. 2318 D.F.

Production. 55 BOP & no wtr. in 8 hrs.
Pmp.

CASING:

8 5/8" 492 cem. w/325 sx.
5 1/2" 3977 cem. w/175 sx.

Figures Indicate Bottom of Formations.

soil & clay	35
sand & shells	105
shale & shells	695
sand & shells	750
shale	1030
sand & shells	1210
sand	1460
shale	1730
lime	1775
shale & shells	2245
lime	2990
shale & shells	3210
shale	3392
lime	3919
lime & chert	3940
lime	4005 RTD
Total Depth	

Tops:

Topeka	3368
Heebner	3567
Lansing	3598
Base K.C.	3836
Simpson	3959
Arbuckle	3977

Meas. from BH to KB 6.48', BH to GL 2.08