

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- STANOLIND OIL & GAS CO.
Farm- V. G. Powers No. 1

SEC. 25 T. 12 R. 22W
SW SE SW

Ogallah Unit 8-1 Was Powers

Total Depth. 4082 P.B. 4054
Comm. 1-26-52 Comp. 2-21-52
Shot or Treated.
Contractor.
Issued. 4-5-52

County Trego
KANSAS



CASING:
8 5/8" 216' cem. w/150 sx.
5 1/2" 4081 cem. w/1100 sx.

Elevation. 2341 RDB
2339 (m)
Production. Swb. 120 bbls.

Figures Indicate Bottom of Formations.

surface sand	100
sand & gummy shale	216
shale & sand	1021
shale & red rock	1725
anhyd.	1780
shale & sand	2065
shale	2315
shale & lime	2595
shale & lime shells	2685
lime & shale	2700
shale	2950
lime & shale	3370
lime	3485
lime & shale	3642
lime	3715
lime & shale	3785
lime	3980
lime & shale	3998
Core # 1	4048
Core # 2	4068 1/2
Quartzites	4078 1/2
Circ.	4082
Total Depth P.B. 4054	

Tops:
Topeka 3367
Mansing 3605
Arbuckle 3997

Core # 1 3998-4048
Rec. 50'; 3998-4004. sdy dolo, bleeding oil except top foot, 3404-07, dolo. bleeding oil, 3407-12', sdy dolo. bleeding oil. 4024-26', gry coarse sand, bleeding oil, 4026-32', scattered bleeding of oil 4045-47', green sdy shale, 4047-48 quartzites, sand, No show
Core # 2 4048-68 1/2
Rec. 20 1/2 Quartzites sand & quartzites.
D.S.T. # 1 3375-3400 tool open 30 mins.
Rec. 185' salt wtr w/light stain. of oil.
BHPSI 1020#.
D.S.T. # 2 3998
tool open 1 hr, rec. 135' oil cut mud, 2085 free oil. Flow press 845#, BHP 1100#.
Perf. 4001-10 and 4016-32', 4 shots per foot.
Perf. 4010-16 4 shots per foot.
Az. Circ 200 gals. 15% acid to bottom.
No surface press.
Zero point 6.65 above center of 3" outlet in 8 5/8" Bradenhead