

24-12-22W F
OJ

JOHN JAY DARRAH, JR.
412 EAST DOUGLAS, SUITE ONE
WICHITA, KANSAS 67202
316/263-2243

August 12, 1985

Kansas Corporation Commission
200 Colorado Derby Building
Wichita, Kansas 67202

AUG 14 1985

Re: API # 15-195-21,662
Bunker #2 - Trego County, Kansas

State Geological Survey
WICHITA BRANCH

Gentlemen: 24-125-22W E/2 NE SW

A formal "Drillers' Log" was not furnished by the rotary contractor. The following information has been taken from the Daily Drilling Report completed by the contractor's crew.

Company: Hess Oil Company Contractor: Robert-Gay Energy Drilling
1006 N. Main
Hutchinson, Kansas 67501

Rig No. 2 Total Depth: 4060' Comm: 4-9-85 Completed: 4-17-85

Well Name: Bunker #2 Description: E/2 NE/4 SW/4 24-125-22W
Trego Co., Kanss

Elevation: 2341 GL 2349 KB

Casing Record: Ran 7 jts. of 8-5/8" tallying 296' set @ 304' KB.
Cemented with 200 sks 60/40 poz, 3% cc, 2% gel by Allied.

Ran 5-1/2" casing, circ. and cement.

Formation	From	To	Remarks
Sand & Shale	0	314	Ran 3 Drillstem Tests
Shale & Sand	314	1240	
Sand	1240	1520	
Shale	1520	2300	
Lime & Shale	2300	2500	
Shale & Lime Streaks	2500	2725	
Shale & Lime	2725	2950	
Lime & Shale	2950	3120	
Lime & Shale Streaks	3120	3300	
Shale & Lime	3300	3455	
Lime & Shale	3455	3595	
Lime & Shale Streaks	3595	3690	
Lime	3690	3712	
Lime & Shale	3712	3720	
Lime	3720	3885	
Lime & Shale	3885	3960	
Lime	3960	4002	
Lime & Shale	4002	4060	