


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- THE TEXAS CO.
 Farm- Christian Church No. 5
 of Ogallah

SEC. 25 T. 12 R. 22W
 SW SW NW

County Trego KANSAS

Total Depth. 4027 PB 4018
 Comm. 1-6-52 Comp. 2-13-52
 Shot or Treated.
 Contractor. Noble Drlg. Co.
 Issued. 3-29-52



CASING:

8 5/8" 496' cem. w/350 sx
 5 1/2" 4014' cem. w/175 sx

Elevation. 2343 DF
 2345 (ad)

Production. Pmp. 26 BO 53 BW
 8 hrs.

Figures Indicate Bottom of Formations.

surface clay & sand	70
sand	175
shale blue	496
shale	560
sand & shale	1565
anhydrite & shale	1920
shale & lime	2415
lime & shale	3150
shale & lime	3470
lime & shale	3510
lime	3663
lime & shale	3720
lime	3783
lime & shale	3850
lime	3918
chert & lime	3995
lime, chert & dolo.	4020
arbuckle	4027
Total Depth PB	4018

Tops:	
Cimarron Anhy.	1754
Topeka	3398
Heebner	3595
Lansing	3626
Basic K.C.	3866
Simpson	3993
Arbuckle	4013