

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- THE TEXAS COMPANY
Farm- V. G. Powers No. 1


SEC. 26 T. 12 R. 22W
NE NE SE

Ogallah Unit 5-1 was V.G. Powers 1

Total Depth. 4040'
Comm. 11-27-51 Comp. 12-20-51
Shot or Treated.
Contractor. Noble Drilling Co.
Issued. 1-26-52

County Trego

KANSAS



CASING:

8 5/8" 508' cemm w/350 sx
5 1/2" 4021' cem. w/175 sx

Elevation. 2365 D.F.

Production. ~~2367 R & 2nd~~
Pot. D.D. 2822 bbls.
oil

Figures indicate Bottom of Formations.

surface clay	40
surface clay & shale	70
sand	200
blue shale	485
shale	533
shale & clay	900
sand	1100
shale	1206
sand	1490
Anhy. & shale	1631
shale	1731
shale & lime	1860
shale	2241
lime & shale	3625
lime	3982
lime & chert	4005
lime	4025, RTD
sand	4040

Total depth:

Tops:

Cimarron Anhy.	1764
Topeka	3401
Heebner	3599
Lansing	3633
Base K. C.	3871
Simpson	4000
Arbuckle	4021

Remarks:

12-29-51 On State Test pumped at following rates:
33 BO per hr for 2 hrs.
12.3 BO per hr for 1 hour
11 BO per hr. for 2 hrs.
Producing horizon Arbuckle 4021-4040,
open hole. Established potential of
2822 BO per day, no wtr.