


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company - THE TEXAS CO.
 Farm - Charles Scott No. 2

SEC. 26 T. 12 R. 22W
 NE SE SE

Total Depth. 4028'
 Comm. 7-4-51 Comp. 8-2-51
 Shot or Treated.
 Contractor. Powell Drlg. Co.
 Issued. 9-8-51

County. Trego KANSAS



CASING:
 10 3/4" 513 cem w/250 sxs.
 7" 4025' cem w/225 sxs.

Elevation. 2346 DF
 2348 RB (and)
 Production. State test estb. pot.
 6323 BOPD

Figures Indicate Bottom of Formations.

surface clay, sand	55
shale, sand	100
shale, shells	513
shale	1145
sand, red bed	1190
sand	1280
red bed, shells	1462
shale, shells	1735
lime	1755
anhydrite	1790
red bed, shale,	
shells	2195
salt	2225
shale, shells	2275
lime, shale	2384
broken lime	2460
lime	2890
lime, shale	2950
shale, shells	3340
shale, lime	3540
lime	3758
lime, chert	3835
lime	3935
lime, chert	3980
lime, shale	3997
lime	4012
dolomite	4028
Total depth	

Tops:	
Heebner	3574
Lansing	3603
Simpson	3969
Arbuckle	3989

Scout top:	
Topeka	3374