

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company- BAY PETROLEUM & BUFFALO OIL CO.
Farm- Tawmoy No. 1

SEC. 27 T. 12 R. 22W
SE SE NE

Total Depth. 4066
Comm. 10-1-52 Comp. 12-1-52
Shot or Treated.
Contractor. Lewis Drilg.
Issued. 12-13-52

County Trego

KANSAS



Elevation. 2376 *2378/2*
State Phys.

Production. 77 BOPD no wtr.

CASING:

8 5/8" 160'
5 1/2" 4052'

Figures Indicate Bottom of Formations.

shale	200
sandy post rock	295
shale	595
shale & sand	1410
sand hrd	1605
shale sdy	1615
shale	1765
Anhyd.	1828
shale & shells	1915
shale & lime strks	2155
shale & shells	2430
shale & brkn lime	2545
shale & lime	2605
lime brkn	3305
lime brkn & shale	3405
lime brkn	3450
lime brkn & shale	3570
lime & shale	3650
lime	3785
shale & chalky lime	3810
lime	3850
shale & lime	3970
Congl.	4015
lime, chert	4027
Congl. shale	4049
lime	4060
Arbuckle	4066
Total Depth	

Tops:	
Topoka	3390
Heebner	3612
Toronto	3631
Lansing	3644
Arbuckle	4047

D.S.T. 3536-3582 rec. 35' mud,
few specks oil, 15" BHP 1160#.

D.S.T. 3639-63 op. 1 hr. rec. 45' mud.
15" BHP 1000 # ..

D.S.T. 3660-92 op. 1 hr. 15" rec. 875'
salt wtr, 1545 # BHP

D.S.T. 4001-27 op 1 hr rec 4' mud. 0 BHP
" 4048-52 op 1 hr rec. 6' VSOCM 0 BHP
" 4050-57 op 1 hr Rec. 2' sli OCM
show from oil 0 BHP

4051-57 op 1 hr. rec. 6' OCM BHP 895 #.

DD to T.D. SSO & DD 4' to 4066 T.D.
1 BOPH net, 500 acid Bail 5 BOPH no wtr.