


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- THE TEXAS COMPANY
 Farm- George Bittel No. 8

SEC. 27 T. 12 R. 22W
 SE SE SE

Total Depth. 4027
 Comm. 7-30-52 Comp. 8-17-52
 Shot or Treated.
 Contractor. Powell Drlg.
 Issued. 9-13-52

County Trego KANSAS



CASING:
 8 5/8" 496 cem. w/325 sx. circ.
 5 1/2" 3992 cem. w/175 sx.

Elevation. 2335 D.F.

Production. D.D. pot. 20,754
 bbls. & no wtr.

Figures Indicate Bottom of Formations.

surface soil & clay	30
sand & shells	110
shale	850
sand	1020
shale & shells	1280
shale	1400
sand	1480
red bed & shale	1570
sand & shale	1610
sand	1650
red bed & shale	1730
anhyd., lime	1835
shale & shells	2210
shale, lime & shells	2300
lime	2375
shale & shells	2500
lime	2890
shale & shells	3180
shale & lime	3270
shale & shells	3481
lime	3925
chert & lime	3964
lime	4027 RTD
Total Depth	

Tops:

CD	1732
Topeka	3367
Heebner	3562
Lansing	3594
Base K.C.	3832
Simpson	3968
Arbuckle	3990

On state test pmp. 20 BCPH for 3 hrs.
 at 20 54" SPM, 15.87 BOPH for 3 hrs.
 at 16 SPM, and 6.21 BOPH for 3 hrs. at
 11 SPM.