


**WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY**  
**508 East Murdock, Wichita, Kansas**

Company- STANOLIND OIL & GAS CO.  
 Farm- R. M. Anderson No. 1  
 "C"

SEC. 34 T. 12 R. 22W  
 NE NE NE

Well Depth. 4065  
 Date 8-11-52 Comp. 9-4-52  
 Drilled or Treated.  
 Drilling Contractor.  
 Completed 10-4-52

County Trego KANSAS



**CASING:**

8 5/8" 199 ccm. w/150 sx.  
 5 1/2" 4064 ccm. w/1100 sx.

Elevation. 2321 RDB

Production. 7771 bbls.

Figures Indicate Bottom of Formations.

surface clay, sand	
& shale	196
shale & shells	220
shale gry	640
shale gry & shells	810
shale & sand	900
shale & shells	980
sand	1045
shale & shells	1240
sand & shale	1520
red bed, shale &	
shells	1722
Anhyd.	1768
shale & shells	1800
shale & shells, red	
bed	2020
shale & lime	3325
lime & shale	3600
lime	3885
lime & shale	3925
lime & shale chert	3937
lime, shale & chert	3990
lime & chert	4045
sand, lime & chert	4065
Total Depth	

Tops:	
Topoka	3362
Heebner	3557
Lansing	3590
Arbuckle	3989

D. S. T. # 1 3983-95 Tool open 1 hr.,  
 rec. 600' sl. mud cut oil, BHP 1095 #,  
 FFP 332#.  
 D.S.T. # 2 3995-4032 Tool open 30 min.,  
 rec. 3120' oil BHP 1122#, FFP 1100#.  
 D.S.T. # 3 4032-4065 Tool open 30 min.,  
 rec. 2550' SW, BHP 1150#, FFP 1150.  
 Perforate 3988-4025. 4 holes per ft.