

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. TENNESSEE GAS TRANS. CO.
Farm. Ellen Hendrickson No. 6

SEC. 35 T. 12 R. 22W
NE NE NE

302 FNL 336 FEL

LED
3/2001
DRL

Total Depth. 4056'

Comm. 6-26-58

Comp. 7-9-58


Shot or Treated.

Contractor. Shelley-Miller Drig.

Issued. 4-11-59

County Trego

KANSAS



Elevation. 2334' RB

Production. 101 BOPD

CASING:

8 5/8" 213.52', cem w/150 sx.

5 1/2" 3455' cem w/125 sx.

Meas. from top of RB

Figures indicate Bottom of Formations.

clay & shale	214
shale & shells	980
sand & shale	1060
red bed	1165
sand	1450
shale & shells	1726
Anhydrite	1765
shale & shells	2067
lime & shale	2520
lime	2560
lime & shale	2735
shale & lime	2905
lime	3000
shale	3045
lime & shale	3285
shale & lime	3330
lime	3945
chert	3960
lime	4035
dolomite	4054
lime	4056 RTD
Total Depth	

TOPS: SCOUT

Topeka 3362

Lansing 3592

Arbuckle 3982