


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 503 East Murdock, Wichita, Kansas

Company- **TENNESSEE GAS TRANS. CO.**
 Farm- **Hendrickson** No. **7**

SEC. **35** T. **12** R. **22W**
 SE NW NE

Total Depth. **4014'**
 Comm. **8-2-58** Comp. **8-12-58**
 Shot or Treated.
 Contractor. **Garvey Drlg.**
 Issued. **6-20-59**

County **Trego**
KANSAS



Elevation. **2296'** **DF**

Production. **72 BOPD, NW**

CASING:

8 5/8" 211' cem w/150 sx.
5 1/2" 4013' cem w/50 sx.

Figures indicate Bottom of Formations.

surface clay & sand	75
shale	160
shale & sandy lime	211
shale, shells, sand	900
sand	1015
shale, shells, sand	1400
shale & sand	1665
red bed & shale	1690
Anhydrite	1735
shale	2350
shale & lime	3140
lime & shale	3331
lime	3381
lime & shale	3455
lime	3910
lime & chert	3985
Arbuckle dolomite	4016
Total Depth	

TOPS: LOG

Topeka (scout)	3332
Heebner	3526
Toronto	3544
Lansing (scout)	3560
Lansing-Kansas City	3558
Base Kansas City (scout)	3801
Marmaton (scout)	3858
Conglomerate (scout)	3886
Simpson (scout)	3929
Arbuckle	3945

DST 3632-49', op 1 hr, rec. 1380' GC
 salt water. IBHP 1335#, FBHP 1294#.

Perf: 3963-60', Acid w/250 gals.