

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


Company. CENTRAL COMMERCIAL CO.
 Farm. U S Government No. 4

SEC. ~~25~~ ³⁵ T. 12 R. 22W
 C NE NW NW
 305 FNL 1010 FSL

(LEO
 3/200
 105-DRL)

Total Depth. 4013
 Comm. 8-4-55 Comp. 8-14-55
 Shot or Treated.
 Contractor. Peel Brothers, Inc.
 Issued. 12-17-55

County Trego KANSAS



Elevation. 2331 DF

Production. 232 BOPD

CASING:

8 5/8 @ 245'
 5 1/2 @ 4012'

Figures Indicate Bottom of Formations.

clay & sand	40
sand & shale	100
shale	165
shale & shells	1542
shale & red bed	1735
anhydrite	1765
shale	1950
shale & shells	2450
shale & lime	3567
lime	3835
red shale	3850
lime & shale	3890
lime	3936
lime & chert	3965
lime & cherty shale	3988
dolomite	4013
Total Depth	

TOPS: (KB)	
Anhydrite	1735
Topeka	3367
Heebner	3562
Lansing	3593
Base K. C.	3830
Arbuckle	3988

DST #1: 3988-4010, open 1 hr. strong
 blow, SI 20 min. rec. 2715' oil,
 IFP 110#, FFP 950#, BHP 1140#