

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


Company- THE TEXAS COMPANY
 Farm- Kellogg-Wynn No. 6

SEC. 36 T. 12 R. 22W
 NW SW NE

Total Depth. 4030
 Comm. 10-29-52 Comp. 12-21-52
 Shot or Treated.
 Contractor. Powell Drilling Co.
 Issued. 3-14-53

County Trego

KANSAS



Elevation. 2328 DF
 Pmp.

Production. 31 BO, 65 BW

CASING:

10 3/4 set at 228' w/ 200 sx cement
 7 in. set at 3980' w/ 175 sx cement

Figures indicate Bottom of Formations.

surface clay & sand	40
sand & shells	110
shale & shells	1300
shale & sand	1475
shale	1735
anhydrite & lime	1775
shale & shells	2300
lime	2750
shale & shells	2985
lime	3100
shale & shells	3215
lime	3295
shale & shells	3350
lime	3910
lime & chert	3980
lime	4030
Total Depth	

TOPS:

Cimarron dolomite	1727
Topeka	3362
Heebner	3563
Lansing	3596
Base KC	3834
Simpson	3962
Arbuckle	3976

Measurement from BH-KB 6.20' BH-GL 1.13'