


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- THE TEXAS COMPANY
 Farm- Kellogg-Wynn No. 9

SEC. 36 T. 12 R. 22W
 NW NE NE

Total Depth. 4003
 Comm. 1-16-53 Comp. 2-8-53
 Shot or Treated.
 Contractor. Powell Drilling Co.
 Issued. 3-14-53

County Trego
 KANSAS



CASING:

10 3/4 set at 239' w/ 200 sx cement
 7 in. set at 3986' w/ 175 sx cement

Elevation. 2304 DF
 2306 (sand)
 Production. Pump 49 BO, 5 1/2 BW

Figures indicate Bottom of Formations.

surface clay, shale & sand	40
shale & shells	239
shale	1000
sand & shells	1220
sand	1475
red bed & shale	1615
shale & shells	1712
lime	1768
shale & shells	2300
lime	3042
shale & shells	3320
lime	3917
lime & chert	3966
lime	4003
Total Depth	

TOPS:

Cimarron dolomite	1714
Topeka	3364
Heebner	3564
Lansing	3596
Base KC	3833
Simpson	3959
Arbuckle	3982

Measurement from BH-KB 5.75' BH-GL 1.00'