


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- THE TEXAS COMPANY
 Farm- Charles Scott No. 1

SEC. 36 T. 12. R. 22W
 SW NW NY

Total Depth. 4024
 Comm. 8-18-51 Comp. 9-25-51
 Shot or Treated.
 Contractor. Powell Prlg Co.
 Issued. 11-10-51

County Trego
 KANSAS



CASING:

10 3/4" 499' cem w/300 sx
 7" 4023' cem w/175 sx

Elevation. 2330 D.F.

2333 (cond)

Production. pmp 107 bbls, no wtr
 in 8 hrs.

Figures Indicate Bottom of Formations.

| | |
|-----------------------|------|
| surface soil, clay | 30 |
| sand | 129 |
| shale, blue | 990 |
| sand | 1060 |
| shale | 1250 |
| sand | 1400 |
| red bed, shale | 1725 |
| anhydrite | 1780 |
| shale | 2000 |
| redbed, shale, shells | 2070 |
| shale | 2380 |
| lime, shale | 2450 |
| lime | 2590 |
| shale, lime shells | 2630 |
| lime | 2685 |
| shale, shells | 3210 |
| lime | 3305 |
| shale, shells | 3410 |
| lime | 3888 |
| lime, shale | 3946 |
| lime, chert | 3987 |
| lime, arbuckle | 4024 |
| Total Depth | |

| | |
|------------------|------|
| Tops: | |
| Topeka | 3366 |
| Heebner | 3565 |
| Lansing | 3598 |
| Base Kansas City | 3837 |
| Simpson | 3964 |
| Arbuckle | 4013 |

RTD 4023