


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL OF KANSAS, INC.  
Farm- Losee No. 1

SEC. 1 T. 12 R. 23W  
NW NW SW

Total Depth. 3759'  
Comm. 8-6-57 Comp. 8-26-57  
Shot or Treated.  
Contractor. Imperial Oil of Kansas, Inc.  
Issued. 11-2-57

County Trego  
KANSAS



CASING:  
8 5/8" 220' cem w/175 sx

Elevation. 2429' RB

Production. 207 BOPD  
6% water

Figures indicate Bottom of Formations.

Sand & clay	115
Shale & shells	575
Sand & shale	1370
Sand	1550
Shale & red bed	1851
Anhydrite	1890
Shale & shells	2420
Shale & lime	3700
Lime	RTD 3756
lime	3759

Total Depth

TOPS:

Anhydrite	1851
Heebner	3636
Toronto	3656
Lansing	3671

DST #1 3643-65 Open 1 hr. rec. 3' mud. BHP 0#

DST #2 3698-3718 Open 2 hrs. Gas to surface in 2 hrs. Rec. 60' heavily oil cut mud, 600' oil, 3' water. BHP 540#

DST #3 3734-56 Open 2 hrs. Rec. 500' gas, 180' heavily oil cut mud, 120' watery mud. BHP 720#