


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- **IMPERIAL OIL OF KANSAS, INC.**
 Farm- **Losee** No. **2**

SEC. **1** T. **12** R. **23E**
 NW NE SW

Total Depth. **3855'**
 Comm. **5-22-60** Comp. **5-31-60**
 Shot or Treated.
 Contractor. **Imperial Oil of Kansas, Inc.**
 Issued. **8-13-60**

County **Trego** **KANSAS**



CASING:

8 5/8" @ 220' w/175 sks. cem.
5 1/2" @ 3854' w/100 sks. cem.

Elevation. **2424' RB**

Production. **195 BOPD**

Figures indicate Bottom of Formation

surface clay & sand	220
shale, sand & shells	1170
shale & sand	1350
Dakota sand	1575
shale & shells	1780
shale & red bed	1836
anhydrite	1880
shale & shells	2405
shale & lime	3575
lime	3855 RTD
Total Depth	

<u>TOPS:</u>	<u>SAMPLE</u>	<u>ELECTRIC LOG</u>
Anhydrite	1836	
Heebner	3618	3618
Toronto	3638	3640
Lansing	3654	3656

Drill Stem Tests:

- #1 3648-60 (Top Zone)
3695-98 (35' Zone)
- #2 3624-48 (Straddle Test-Toronto)
3654-65 (Top Zone)
- #3 3677-3705 (35' Zone)
3710-16 & 3718-20 (50' Zone)
- #4 3712-24 (50' Zone)
3730-34 (70' Zone)
3740-47 (90' Zone)
3751-57 (100' Zone)
- #5 3752-59 (100' Zone)
3801-05 (140' Zone)
3821-27 (160' Zone)
3841-46 (180' Zone)