


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL OF KANSAS, INCORPORATED  
Farm- Hixson "D" No. 4

SEC. 2 T. 12 R. 23W  
C E/2 NW SE

Total Depth. 3900:  
Comm. 3-5-57 Comp. 3-15-57  
Shot or Treated.  
Contractor. Imperial Oil of Kansas, Incorporated  
Issued. 5-18-57

County Trego KANSAS



Elevation. 2422' RB

**CASING:**

8 5/8" @195' w/150 sx cem.

Production. Dry

Figures indicate Bottom of Formations.

sand & shale	195
shale & shells	955
shale, shells & sand	1834
Anhydrite	1887
shale & shells	2425
shale & lime	3682
lime	3900 RTD
Total Depth	

TOPS	
Anhydrite	1834
Heebner	3635
Toronto	3654
Lansing	3667

**DRILL STEM TESTS**

DST #1 3641-65' op. 40 min.  
Rec. 5' mud. BHP 510#.  
DST #2 3696-3727' op. 2 hrs.  
Rec. 105' salt water. BHP 460#.  
DST #3 3735-50' op. 1 hr.  
Rec. 30' mud BHP 640#.  
DST #4 3747-58' op. 1 hr.  
Rec. 15' mud. BHP 560#.