


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. IMPERIAL OIL OF KANSAS, INC.
Farm. Hixson "B" No. 1

SEC. 11 T. 12 R.23W
NE NE NW

Total Depth. 3738
Comm. 8-29-56 Comp. 9-17-56
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 10-27-56

County Trego
KANSAS



CASING:
8 5/8" 229' cem w/175 sx.
5 1/2" 3732'

Elevation. 2419 R.B.

Production. 2200 BOPD, no water

Figures indicate Bottom of Formations.

clay, sand, shells	229
shale, sand	1010
sand, pyrite	1090
shale, shells	1330
sand Dakota	1550
shale, shells	1810
shale, red bed	1838
anhydrite	1880
shale	1975
shale, lime	3526
lime	3738

Total Depth

Tops:
Anhydrite 1838
Heebner 3628
Toronto 3648
Lansing 3660

Drill Stem Tests:

- #1 3635-60 Open 2 hrs. Rec. 120' gas
70' heavily oil cut mud, & 30' muddy
water. FP 0-50#. BHP 1025#.
- #2 3661-72 Open 1 hr. Rec. 210' salt
water with a slight show of oil.
FP 0-105#. BHP 1255#.
- #3 3689-3710 Open 1 hr. Rec. 1200' gas,
125' heavily oil cut mud, 200' oil,
FP 30-130#. BHP 1050#.
- #4 3713-32 Open 1 hr. Rec. 585' gas, 65'
oil, 210' oil cut water. FP 30-160#.
BHP 1155#.