

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL OF KANSAS, INC.
 Farm- Newcomer "A" No. 2


SEC. 12 T. 12 R. 23W
 SW NE SW

Total Depth. 3872'
 Comm. 4-26-56 Comp. 5-11-56
 Shot or Treated.
 Contractor. Imperial Oil of Kansas, Inc.
 Issued. 7-14-56

CASING:

8 5/8" 196' w/175 sx cem.

County Trego
 KANSAS



Elevation. 2125' RB

Production. 444 BOPD

Figures indicate Bottom of Formations.

clay-shells-sand	185
shale-shells	250
shale sand-shalle	710
Dakota sand	950
shale shells-sand	1834
Anhydrite	1875
shale-shells	2420
shale-lime	3519
lime	3872
Total Depth	

TOPS:

Anhydrite	1834
Heebner	3638
Toronto	3656
Lansing	3670

DST #1 - 3643-67 Open 2 hrs.,
 rec. 150' very heavy
 OCM. FP 20#-50# BHP 435#

DST #2 - 3700-19 Open 1 hr, rec.
 570' gas, 70' slightly
 OCM, 70' heavy OCM. FP
 0#-50# BHP 1000#.

DST #3 - 3719-30 Open 1 hr., rec.
 300' wtr., no oil. FP 0#-
 150# BHP 1180#.

DST #4 - 3740-52 Open 1 hr., rec.
 2450' gas, 460' oil, FP
 0#-180# BHP 1180#.

DST #5 - 3755-59 Open 1 hr., rec.
 150' gas, 30' OCM, 120'
 wtr, FP 0#-80# BHP 1210#.

DST #6 - 3768-74 Open 1 1/2 hrs., rec.
 140' wtr. FP 0#-50# BHP
 1210#.

DST #7 - (140', 160', 180' zones)
 3800-72 Open 1/2 hr., rec.
 6' mud. BHP 50#.