


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PHILLIPS PETROLEUM
Farm- Rasck "A" No. 2

SEC. 12 T. 12 R. 23W
SE NW SE

Total Depth. 3916' TB 3726' PB
Comm. 6-1-56 Comp. 6-26-56
Shot or Treated.
Contractor.
Issued. 8-25-56

County Trego KANSAS



Elevation. 2100' DL

Production. 403 BOPD & NW

Figures indicate Bottom of Formations.

sand & shale	317
shale	467
shale, sand	
& lime streaks	1807
Anhydrite	1842
lime & shale	2445
lime	2695
lime & shale	2944
lime	3044
lime & shale	3453
lime	3887
lime & shale	3916 Corrected
Total Depth	
PB	3726

TOPS:
Howard 3394
Topeka 3420
Heebner 3614
Toronto 3633
Lansing-Kansas
City 3647
Base Kansas City 3894
Marmaton 3901

PB 3835, Perf. 3730-36 last hr. 5 BW
w/scum of oil, Drill out
cem. 3726

Perf. 3723-27, acid w/500 gals.
acid w/250 gals. Sub. 167 BO
& 30 BW 4 hrs.

Perf. 3688-92, set boker plug
3710 acid w/500 gal. Sub 98 BO
& 8 BW 4 hrs. C.O. 3726