


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PHILLIPS PETROLEUM COMPANY
Farm- Basek "A" **No.** 3

SEC. 12 **T.** 12 **R.** 23W
 NW SW SE

Total Depth. 3916' **PB** 3761'
Comm. 6-12-56 **Comp.** 7-16-56
Shot or Treated.
Contractor.
Issued. 8-25-56

County Trego **KANSAS**



CASING:
 9 5/8" 3261/2' w/195 sx
 5 1/2" 3879' w/120 sx

Elevation. 2394' ~~DI~~

Production. 210 BO & 256 BW

Figures indicate Bottom of Formations.

sand & shale	317
shale	474
sand & shale	1200
shale, sand & lime	1694
lime & shale	2477
lime	2741
lime & shale	3054
lime	3308
lime &	
shale streaks	3473
lime	3882
lime & shale	3916
Total Depth	
Cable Tool	PB 3761
TOPS	

Howard	3386
Topeka	3413
Heebner	3603
Toronto	3623
Lansing-Kansas	
City	3637
Drum	3780
Base-Kansas City	3880
Marmaton	3889

C. O. to 3846, Perf 3794-3804, acid
 500 gal. balled .74 BO & 7.19
 BW 11 1/2 hrs.

Perf 3738-45, w/boker ret. plug 3770,
 acid w/500 gal. Sub 92 BO & 3 7 1/2
 BW 4 hrs. Rec. plug. set plug &
 dumped calseal to 3730

Perf 3713-17 set plug @ 3730 Sub 119 BO
 & 103 1/2 BW 8 hrs. Retrived plug
 3730 set boker plug @ 3705

Perf 3694-96, acid w/500 gals. Sub 65 1/2
 BO & 29 1/2 BW Jrone plug 3706-3761

Perf 3679-82, acid w/3000 gals, all
 perforations comp. for above
 patented.