


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL OF KANSAS, INC.
 Farm- Rhoden "C" No. 1

SEC. 14 T. 12 R. 23W
 NE NE SE

Total Depth. 4250'
 Comm. 4-17-56 Comp. 4-29-56
 Shot or Treated.
 Contractor. Imperial Oil of Kansas, Inc.
 Issued. 6-23-56

County Trego KANSAS



CASING:
 8 5/8" 198' cem w/175 sx

Elevation. 2138' KB

Production. Dry

Figures indicate Bottom of Formations.

sand and shells	196
shale	1858
anhydrite	1900
shale and shells	2540
lime and shale	3530
lime	4207
Arbuckle	4250
Total Depth	

Tops:	
Anhydrite	1858
Heebner	3671
Toronto	3691
Lansing	3704
Base Kansas City	3955
Marmaton Cherty Lime	4022
Conglomerate	4150
Arbuckle	4198

DST #1 3732-50', tool open 1 hr., rec. 10'
 of mud with few specks of oil. BHP 35# in
 20 mins.

DST #2 3750-70', tool open 30 mins., rec. 11'
 of mud. BHP 1140# in 20 mins.

DST #3 3767-97', tool open 1 hr., rec. 330'
 of salt water, no oil. IF 65#, FF 260#,
 BHP 1215# in 20 mins.

DST #4 3839-3902', tool was open 35 mins.
 Rec. 10' of mud. BHP 410#.

DST #5 4055-4140', tool open 1 hr., rec. 31'
 of mud, BHP 770# in 20 mins. There was no
 sand development in the Marmaton section.

No electric log run.