

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Rhoden "A" No. 4

SEC. 24 T. 12 R.23W
NE SW NE

Total Depth. 3762
Comm. 9-28-56 Comp. 10-18-56
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 12-29-56

County Trego

KANSAS



Elevation. 2421' RB

Production. 124 BOPD-8% wtr.

CASING:

8 5/8" 194' w/150 sx cem.
5 1/2" @3761'

Figures indicate Bottom of Formations.

surface sand-clay	194
sand-shale	1315
Dakota sand	1555
shale-shells	1645
shale-red bed	1835
Anhydrite	1879
shale-shells	2205
shale-lime	3584
lime	3761 RTD
lime	3762
Total Depth	

TOPS:

Anhydrite	1835
Heebner	3655
Toronto	3665
Lansing	3680

DST # 1 - 3652-77 Open 2 hrs.
Rec. 630' gas, 450' oil & MCO.
FP 0-190#. BHP 800#.

DST # 2 - 3674-3708 Open 1/2 hr.
Rec. 15' oil & salt wtr. CM.
BHP 190#.

DST # 3 - 3709-28 Open 3 hrs.
Rec. 210' gas, 30' OCM. FP 0-20#.
BHP 305# (still building up)

DST # 4 - 3726-44 Open 1 hr.
Rec. 350' gas, 140' oil & OCM,
120' salt wtr. FP 0-95#. BHP 1005#.

DST # 5 - 3743-57 Open 1 hr.
Rec. 2' oil, 5' HOCM. BHP 20#.

DST # 6 - 3756-61 Open 1 hr.
Rec. 5' OCM. BHP 20#.