


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Rhoden "A" No. 5

SEC. 24 T. 12 R. 23W
SW SE NE

Total Depth. 4180'
Comm. 10-8-56 Comp. 11-2-56
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 12-29-56

County Trego KANSAS



CASING:
8 5/8" 193' w/150 sx cem.
5 1/2" @4180'

Elevation. 2399' RB

Production. 104 BOPD, NW

Figures indicate Bottom of Formations.

surface sand-shale	193
sand-shale	1290
Dakota sand	1530
shale-red bed	1813
Anhydrite	1855
shale-shells	2205
shale-lime	3584
lime	4180
Total Depth	

TOPS:	
Anhydrite	1813
Heebner	3628
Toronto	3654
Lansing	3662
Marmaton cherty lime-	
stone	3883
Cherty Conglomerate	4069
Arbuckle	4154

DST # 1 - 3657-82 Open 1/2 hr.
Rec. 15' mud w/a very slight
show oil. BHP 1140#.

DST # 2 - 3682-3712 Open 2 hrs.
Rec. 1080' gas, 150' MCO, 150'
clean oil. FP 0#-110#. BHP 1175#.

DST # 3 - 3710-27 Open 1 hr.
Rec. 600' gas, 150' MCO, 60'
clean oil. FP 40-110#. BHP 1040#.

DST # 4 - 3724-42 Open 2 hrs.
Rec. 300' gas, 60' HOCM, 60' MCO.
FP 0#-80#. BHP 1205#.

DST # 5 - 3740-54 Open 1 hr.
Rec. 140' OCM, 120' oil, 550'
OCSW, 6' salt wtr. FP 40#-360#.
BHP 1070#.

DST # 6 - 4048-97 Open 1/2 hr.
Rec. 20' rotary mud. No shows.
BHP 605#.