


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. IMPERIAL OIL OF KANSAS, INC.
Farm. Rhoden "B" No. 1

SEC. 24 T. 12 R. 23W
C N/2 N/2 SE

Total Depth. 3915
Comm. 5-19-57 Comp. 6-1-57
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 7-6-57

County Trego
KANSAS



CASING:
8 5/8 @ 219' w/ 175 sx cmt.
4 1/2 @ 1835'

Elevation. 2405 RB

Production. SWDW

Figures indicate Bottom of Formations.

shale & sand	219
shale & shells	650
sand & shale	1150
shale, shells & sand	1770
shale & shells	1820
anhydrite	1860
shale & shell	2420
shale & lime	3695
lime	3915
Total Depth	

TOPS:

Anhydrite	1820
Heebner	3632
Toronto	3654
Lansing	3669
Base KC	3911

DST #1: 3698-3718, open 1 hr. rec.
385' wtr. w/ tr. oil. BHP 1450#

DST #2: 3724-29, open 2 hrs. rec.
85' OCW, BHP 565#

DST #3: 3738-49, open 1 hr. rec. 7'
mud w/ tr. oil. BHP 10#

DST #4: 3747-55, open 2 hrs. rec.
220' gas, 30' muddy oil, 50' HOCM,
w/ sl. show wtr. 120' wtr. BHP 990#

DST #5: 3660-96, straddle test, open
2 hrs. rec. 230' muddy wtr. no oil
show, BHP 930#