

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL OF KANS., INC.
Farm- Rhoden "B" No. 2

SEC. 24 T. 12 R. 23W
NE NE SE

Total Depth. 3757'

Comm. 6-1-57

Comp. 6-18-57


Shot or Treated.

Contractor. Imperial Oil of Kans., Inc.

Issued. 9-7-57

County Trego

KANSAS



Elevation. 2414' RB

Production. 171 BOPD, 51% Wtr.

CASING:

8 5/8" 214' cem w/175 sx.
5 1/2" 3751½' cem.

Figures indicate Bottom of Formations.

sand & shale	825
sand, shale & shells	1824
anhydrite	1868
shale & shells	2420
shale & lime	3650
lime	3751½ RTD
lime	3757
Total Depth	

TOPS:

Anhydrite	1824
Heebner	3638
Toronto	3657
Lansing	3672

DST #1 3666-98' open 1 hr., rec. 12' mud
with specks of oil. BHP 160#.

DST #2 3698-3720' open 2 hrs., rec. 300'
gas, 130' heavily oil cut mud.
BHP 800#.

DST #3 3719-36' open 1 hr., rec. 180'
muddy oil, 540' gas. BHP 780#.

DST #4 3735-49' open 1 hr. Rec. 15' mud.
BHP 460#.