

Operator
 Rains & Williamson Oil Co., Inc. DESIGNATE TYPE OF COMP.: OIL, GAS,
 DRY HOLE, SWDW, ETC.:
 Dry Hole

Well No. 1 Lease Name Deines

S 26 T 12 R 23 W SW NE SE

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<u>LOG TOPS</u>				
DST #1, 3754-3772 Open 30, shut in 30, open 60, shut in 30. Strong Blow. Rec. 1900' saltwater. FP 62-902, IBHP 1068, FBHP 1057. DST #2, 3787-3805 Open 30, shut in 30, open 60, shut 30. Strong Blow. Rec. 1560' saltwater. BHP's 1171-1167. FP's 52-800 DST #3, 3858-3904 Open 30, shut in 30, open 30, shut in 30. Weak blow for 30 min. & died. Rec. 40' mud with oil spots. BHP's 1140-975, FP's 18-41.			Anhydrite	1801 +540
			B/Anhydrite	1845 +496
			Heebner	3669 -1328
			Toronto	3691 -1350
			Lansing	3706 -1365
			Base Kansas City	3967 -1626
			Pawnee	4061 -1720
			Conglomerate Sd.	4185 -1844
			Shaley Miss.	4214 -1873
			Clean Miss.	4221 -1880
			Gilmore City	4283 -1942
			Viola	4375 -2034
			Simpson Shale	4442 -2101
		Arbuckle	4447 -2106	
		LTD	4457 -2116	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Wilson Rains

 Signature Wilson Rains

 President
 Title

 December 6, 1973

 Date

QSBEO1