

PC

June, 1940.

(Rasek)

Trigg #1 Pasek,
C NE NE, 13-12S-23W,
Elevation 2417'.

Pennsylvanian conglomerate 4115-4128'
4115-4128 Conglomerate of stained chert with some
interbedded sand. Much of the chert is
of Cottertype.

Arbuckle Top 4128' Penetration 77' Sub-sea, minus 1711'
4128-4205 Pre-Cotter dolomite. White, mainly coarsely
crystalline, with very little chert. This
sequence is probably the upper part of the
Pre-Cotter.

On an Arbuckle datum this test is at least
200' higher than the test in the C SE NW,
14-12S-23W.