

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

SIDE ONE

1-12-25w Compt. 71

(Rules 82-3-130 and 82-3-107)

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

F Letter requesting confidentiality attached.

C Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE #	6114	EXPIRATION DATE	6-30-84
OPERATOR	Don E. Pratt Oil Operations	API NO.	15-195-21,376
ADDRESS	Box 370	COUNTY	Trego
	Hays, Kansas 67601	FIELD	Hladek
** CONTACT PERSON	Susie Ubert	PROD. FORMATION	LKC
	PHONE. 913-625-3446		
PURCHASER	Koch Oil Co.,	LEASE	Hobbs
ADDRESS	Box 2256	WELL NO.	4 - 1
	Wichita, KS 67201	WELL LOCATION	110' N & 110' W of SE SE NW
DRILLING CONTRACTOR	Foxfire Drilling Company		2200 Ft. from North Line and
ADDRESS	10403 W. Colfax		2200 Ft. from West Line of
	Lakewood, Colorado 80215		the NW (Qtr.) SEC 1 TWP 12S RGE 25 (W).
PLUGGING CONTRACTOR	N / A	WELL PLAT	(Office Use Only)
ADDRESS			KCC
			KGS
			SWD/REP
			PLG.
			NGPA
TOTAL DEPTH	4175	PBTD	
SPUD DATE	11/13/83	DATE COMPLETED	11/19/83
ELEV: GR	2515	DF	2520
		KB	2522
DRILLED WITH (CABLE)	(ROTARY)	(AIR)	TOOLS.
DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE			

Amount of surface pipe set and cemented 249' DV Tool Used?

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - (Oil) Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion. Other completion. NGPA filing.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Steven D. Pratt, General Mgr., being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

103514

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR Don E. Pratt Oil Operations LEASE Hobbs SEC. 1 TWP. 12S RGE. 27 (W)

HILL IN WELL INFORMATION AS REQUIRED:

WELL NO. 4 - 1

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Check if no Drill Stem Tests Run.				
Check if samples sent to Geological Survey				
Sand & Shale	0	2113	Topeka....	-1088...3610
Anhydrite	2113	2155	Heebner...	-1315...3837
Shale	2155	2777	Toronto...	-1336...3858
Shale & Lime	2777	3679	Lans.KC...	-1350...3872
& Shale	3679	4175	Base KC...	-1597...4119
			R.T.D.....	-1653...4175
			L.T.D.....	-1650...4172
DST#1., 4033-4075 open 90 minutes rec. 3150' gas, 930' MO Flow pressure to 319 pounds, '30 min IBHP 991 pounds Final BHP 956 lbs.,				

ACID, FRACTURE FLOO, CEMENT SQUEEZE RECORD

Amount and kind of material used			Depth interval treated	
2000 gals. SGA-15%			4040-4050	
Date of first production			Producing method (flowing, pumping gas lift, etc.)	
12-4-83			Gravity	
Gas	Oil	Water	Gas-oil ratio	CFPB
12-4-83	60 b.o.p.d.	10 %		
Definition of gas (vented, used on lease or sold)			Perforations	

of all strings set—surface, intermediate, production, etc. CASING RECORD (New) or (Used)

of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8 5/8"	24#	256'	Class A	150	2% gel, 3% CC
Production	7 7/8"	4 1/2"	10.5#	4174'		200	

LINER RECORD

PERFORATION RECORD

Top ft	Bottom ft	Sacks cement	Shots per ft	Size & type	Depth interval
			4	SDJ	4040-4050

TUBING RECORD

Setting depth