


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas

Company- D.R. LAUCK OIL CO., INC.  
 Farm- Martin No. 2

SEC. 36 T. 12 R. 28W  
 C SW NE

Total Depth. 4445'  
 Comm. 9-16-65 Comp. 9-28-65  
 Shot or Treated.  
 Contractor. Co. Tools  
 Issued. 2-5-66

County Gove KANSAS



**CASING:**

8 5/8" 216' w/165 sx cem.

Elevation. 2577' DE

Production. DRY

Figures Indicate Bottom of Formations.

shale	800
sand	950
shale	1415
shale, lime	1639
sand, shale	1795
shale, shells	2059
Anhydrite	2135
lime, shale	3100
lime	3195
lime, shale	3758
lime	3960
lime, cherty	4005
lime	4039
lime, shale	4135
lime	4195
shale, lime	4266
lime	4393
Dolomite	4445 RTD
Total Depth	

TOPS:	SAMPLES WELEX	
Heebner	3724	3719
Toronto	3745	3743
Lansing	3764	3762
B/Kansas City	4049	4039
Marmaton	4073	4071
Cherokee shale	4241	4236
C onglomerate	4335	4332
Mississippian	4344	4342
Watsaw	4344	4342
Osage	4368	4370

DST #1 (S) 4328-55, Op. 1 hr., weak blow 20 min., very weak blow 40 min. Rec. 57' oil & GCM w/estimated 1 gal. free oil in tool. ISIP 838#, 30 min. FSIP 219#, 30 min. IFP 28#, FFP 38#.

DST # 2 (S) 4328-65, Op. 1 hr., weak blow 40 min., weak intermittent blow 20 min. Rec. 70' slightly oil & GCM. ISIP 1466#, 30 min. FSIP 727#, 30 min. IFP 19#. FFP 47#

DST #3 (S) 4327-80, Op. 1 hr., weak blow 35 min., weak intermittent blow 25 min. Rec. 40' drilling mud. SIP 1355#, 30 min. FSIP 783#, 30 min. IFP 19#, FFP 47#.