

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- RUDY HERMAN OIL OPERATIONS  
 Farm- Meckel "B" No. 3

SEC. 29 T. 12 R. 156W  
 SE NE NE

Total Depth 3405' Rotary Depth 3340  
 Comm. 6-4-59 Comp. 6-16-59  
 Shot or Treated.  
 Contractor Shields Drlg. Co.  
 Issued. 2-11-61

County Russell  
 KANSAS



CASING:

8 5/8" 912' cem w/450 sx.  
 5 1/2" 3339' cem w/125 sx.

Elevation. 1852' DF

Production. 160 BOPD

Figures Indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE:

DST #4 3268-3300', op 1 hr, strong blow thruout test, rec. 60' heavy oil cut mud, 1440' clean oil. IFP 115#, FFP 600#, BHP 905#/30 mins.

2975-2979 occasional lgt brn oil stain in white crystalline limestone

DST #5 3300-3310', op 1 hr, fair blow thruout test, rec. 80' oil & 40' water IFP 16#, FFP 65#, BHP 877#/30 mins.

3007-3013 scattered lgt brn oil stain in buff crystalline limestone

TOPS: SAMPLE

Anhydrite (Driller)	902
Topeka	2732
Heebner	2953
Toronto	2971
Lansing-Kansas City	3002
Conglomerate	3276
Arbuckle	3284

3030-3034 scattered rich brn oil stain in buff crystalline limestone

3046-3051 scattered lgt brn oil stain in white to buff crystalline & oolitic limestone

3078-3082 very rare trace of lgt brn oil stain in white crystalline limestone

3094-3097 occasional lgt brn oil stain in buff crystalline limestone

3097-3104 scattered lgt brn oil stain in buff oolitic limestone

3193-3195 very rare trace of lgt brn oil stain in buff oolitic limestone

3263-3267 very rare trace of lgt brn oil stain in buff crystalline limestone

3276 white opaque, sharp chert w/a trace of lgt brn oil staining

3284-3299 white to buff medium crystalline dolomite w/scattered rich brn oil stain

3299-3310 buff medium to coarse crystalline dolomite, rich brn oil saturation

3310-3340 dense white dolomite, no show oil.

Rotary Total Depth 3340 -  
 Total Depth 3405 -

DST #1 2985-3018', op 1 hr, good blow thruout test, rec. 660' gas in drill pipe, 180' heavy oil & gas-cut mud. IFP 0#, FFP 32#, BHP 308#/30 mins.

DST #2 3018-3037', op 1 hr, good blow thruout test, gas to surf. in 47 mins, rec. 150' heavy oil & gas-cut mud, 490' oil. IFP 0#, FFP 73#, BHP 317#/30 mins.

DST #3 3040-3058', op 1 hr, strong blow thruout test, gas to surf in 13 mins, rec. 1240' light gassy oil. IFP 150#, FFP 400#, BHP 450#/30 mins.