


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS CO.
Farm - Federal Farm & Mort. Corp. No. 1.

SEC. 17 T. 12 R. 30 W
NW NE SE

Total Depth. 4902 PB 4016
Comm. 7-27-44 Comp. 10-6-44
Shot or Treated.
Contractor. Parker Drilg. Co.
Issued. 1-20-45 Rotary O-4902

County. Gove
KANSAS



CASING:
8 5/8" 1889' Cem.
5 1/2" 4200' Cem.

Elevation. _____

Production. Dry

Figures indicate Bottom of Formations.

surface soil	10	oil - Acidize w/500	
sand & gravel	90	gals, 2000' wtr.	
sand & shale	110		
shale	130	Tops:	
gravel	230	Anhydrite	2340
gravel & shale	410	Topeka	3660
shale & sand	1065	Lansing	3898
shale & shells	1275	Miss.	4484
shale & sand	1460	Arbuckle	4810
shale & shells	1495		
shale & sand	1775		
sand & shale	1850	Dry & Abnd.	
shale & shells	1875		
red bed	1890		
shale, shell, red bed	2070		
shale	2190		
shale & shells	2345		
anhydrite	2392		
red bed & shells	2580		
red bed & shale	2655		
lime brkn	2790		
lime brkn & shale	3210		
lime brkn	3300		
lime	3375		
lime brkn	3455		
lime	4406		
chert & lime	4415		
lime	4460		
lime & shale	4500		
lime	4622		
lime & chert	4640		
chert	4668		
lime	4844		
lime cherty	4902		
Total Depth			
P.B.T.D.	4016		

Perf 3148-57 w/32 shots,
acidized w/1000 gals,
3/4 BWPB - Lane-Wells
plug set @ 4100' -perf
3998-4002 w/12 shots,
2000' wtr & 100' oil
squeeze perf - Perf 3998-4002
w/12 shots, no show
acidized w/500 gals,
2000' wtr & rainbow
oil - squeeze perf -
Perf 3998-4002 w/15
shots, 200' wtr & show
oil, acidized w/500
gals, 2200' wtr &
show oil - squeeze
perf - Perf 3899 w/3
shots 1100' fluid in
1 1/2 hrs, some free oil -
squeeze perf - Perf
3899-98 1/2 w/13 shots,
1/2 B. fluid & show of