

15-063-20359

State Geological Survey

WICHITA BRANCH
KANSAS DRILLERS LOG

API No. 15 — County — Number —

Operator
Donald C. Slawson

Address
200 Douglas Bldg., Wichita, Kansas 67202

Well No. 1 Lease Name Weber 'K'

Footage Location
1310' feet from (N) (S) line 650' feet from (E) (W) line

Principal Contractor Slawson Drilling Co., Inc. Geologist Dick Roby

Spud Date August 27, 1977 Total Depth 4590 P.B.T.D. N/A


Date Completed September 4, 1977 Oil Purchaser N/A

S. 13 T. 12 R. 31W E

Loc. E/2 NE

County Gove

640 Acres
N



Elev.: Gr. 2901

DF 2903 KB 2906

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$ "	8 5/8"	28#	298'	60/40 poz	225	2% gel, 3% cc

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated


INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio	CFPB

Disposition of gas (vented, used on lease or sold) Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Donald C. Slawson		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: dry hole	
Well No. 1	Lease Name Weber 'K'		
S <u>13</u> T <u>12</u> R <u>31W</u> E W			
WELL LOG Show all important zones of porosity and contents thereof; cased intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC. 0 - 305 Surface hole 305 - 700 Shale and shells 700 - 1650 Shale 1650 - 1920 Sand 1920 - 2400 Shale and shells 2400 - 2456 Anhydrite 2456 - 2486 Shale and lime 2486 - 3130 Shale 3130 - 3820 Shale and lime 3820 - 4325 Lime 4325 - 4550 Lime and shale 4550 - 4590 Lime 4590 RTD DST #1 3916-3950 (TORO), 30-45-45-60, SI Rec. 2' OCM, 440' MSW, IFP 40-131#, ISIP 1209#, FFP 152-243#, FSIP 1179# DST #2 3975-3996 (35' zn), 30-30-30-30, Rec. 10' M, IFP 20-30#, ISIP 1169#, FFP 40-40#, FSIP 1099#, 104° DST #3 4013-4034 (70' zn) 30-30-30-30, Rec. 3' M, SSO, IFP 30-30#, ISIP 101#, FFP 30-30#, FSIP 50#, 103° DST #4 4145-4180 (180' zn) 30-45-45-45, Rec. 60' Tn mud, IFP 40-60#, ISIP 1259#, FFP 61-81#, FSIP 1189#	TOP	BOTTOM	NAME LOG TOPS ANH 2397 (+509) B/ANH 2424 (-482) HEEB 3905 (-99) TORO 3926 (-1020) LANS 3948 (-1042) STK 4175 (-1269) L/CK 4456 (-1550) MISS 4508 (-1602) LTD 4586
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature R.J. Thatcher Title September 13, 1977 Date		

878991

WELL LOG

OPERATOR: Donald C. Slawson
200 Douglas Building
Wichita, Kansas 67202

LEASE: #1 Weber 'K'
E/2 NE Sec. 13-12-31W
Gove County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.

COMMENCED: August 27, 1977

COMPLETED: September 4, 1977


CASING: Set 8 5/8" @ 298' w/225 sx 60/40 Poz

0 - 305	Surface hole
305 - 700	Shale and shells
700 - 1650	Shale
1650 - 1920	Sand
1920 - 2400	Shale and shells
2400 - 2456	Anhydrite
2456 - 2486	Shale and lime
2486 - 3130	Shale
3130 - 3820	Shale and lime
3820 - 4325	Lime
4325 - 4550	Lime and shale
4550 - 4590	Lime
4590	RTD

STATE OF KANSAS)
)
COUNTY OF SEDGWICK)

SS.

I, R.J. Thatcher, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Weber 'K' test.


R.J. Thatcher