

SIDE ONE

WELL COMPLETION OR RECOMPLETION FORM
ACO-1 WELL HISTORY

```
Operator: license # 5023
name Kansas Petroleum, Inc.
address 225 N. Market, Suite 310
City State Zip Wichita, KS 67202
```

Operator Contact Person ... James Tasheff.....
Phone 267-2266.....

Contractor: license # 5651
name Mallard Drilling Company.....

Wellsite Geologist ... William Shepherd
Phone 263-5495

PURCHASER N/A

Designate Type of Completion		
New Well	Re-Entry	Workover

SWD	Temp Abd
Inj	Delayed Comp.
Other (Core, Water Supply etc.)	

If **OWWO**: old well into as follows:

Operator
Well Name
Comp. Date Old Total Depth

Drilling Method.	☒ Mud Rotary	☐ Air Rotary	☐ Cable
------------------	--	-------------------------------------	--------------------------------

6/23/84	6/30/84	6/30/84
Spud Date	Date Reached TD	Completion Date

...4765.--. ...
Total Depth PRYD

Amount of Surface Pipe Set and Cemented at 260 feet

Multiple Stage Cementing Collar Used? : Yes ☐ No ☒

If Yes, Show Depth Set feet

If alternate 2 completion, cement circulated
from feet depth to w/ SX cmt

will be by record

API NO. 15 - 109-20,330

County Logan

...SE NW NE. Sec. 3.... Twp. 12... Rge. 32... West
(location)

...4290... Ft North from Southeast Corner of Section
...1650... Ft West from Southeast Corner of Section
(Note: locate well in section plat below)

Lease Name: Moeder Well# 1

Field Name Wildcat

Producing Formation Mississippi.....

Elevation: Ground 3027 KB 3035

Section 1st lat

WATER SUPPLY INFORMATION

Source of Water:

Division of Water Resources Permit # T-84-351

X. Groundwater.	4290		Fl North From Southeast Corner and
(Well)	1650		Fl. West From Southeast Corner of
	Sec	Twp	Rge East West

_____ Surface Water, ... Ft North From Southeast Corner and
 (Stream, Pond etc.) Ft West From Southeast Corner
 Sec Twp Rge East West

Other (explain)
(purchased from city, R.W.D.#)

Disposition of Produced Water:	Disposal
	Repressuring

Docket #
N/A

INSTRUCTIONS: This form shall be completed in duplicate and filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202 within 90 days after completion or recompletion of any well. Rules 82-3-130 and 82-3-107 apply.

Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form. See rule 82-3-107 for confidentiality in excess of 12 months.

107407

SIDE TWO

Operator Name Kansas Petroleum, Inc. Lease Name Moeder Well# 1 SEC. 3 TWP. 12 RGE. 32W☐ East
☐ 1

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken

☐ Yes ☒ No

Samples Sent to Geological Survey

☒ Yes ☐ No

Cores Taken

☐ Yes ☒ No

Formation Description

☒ Log ☐ Sample

Name	Top	Bottom
Anhydrite	2572	+463
Heebner	4030	-995
Toronto	4059	-1024
Lansing-K.C.	4073	-1038
B/K.C.	4366	-1331
Marmaton	4397	-1362
Pawnee	4507	-1472
Fort Scott	4563	-1528
Cherokee	4586	-1551
Mississippi	4713	-1678
RTD	4766	-1731

CASING RECORD

☒ new☐ used

Report all strings set - conductor, surface, intermediate, production, etc.

Purpose of string	size hole drilled	size casing set (in O.D.)	weight lbs/ft.	setting depth	type of cement	# sacks used	type and percent additives
Surface	12 1/4	8 5/8	24	260	Pozmix/ Common	100 100	2% gel, 3% CC

PERFORATION RECORD

shots per foot

specify footage of each interval perforated

Acid, Fracture, Shot, Cement Squeeze Record

(amount and kind of material used)

Depth

	N/A	N/A	

JUL 12 81

D R I L L E R S L O G

COMPANY: Kansas Petroleum, Inc.

WELL NAME: #1 Moeder

TRACTOR: MALLARD DRILLING CO., INC.
405 CENTURY PLAZA BLDG.
WICHITA, KANSAS 67202

DESCRIPTION:

SE NW NE 3-12S-32W

RIG NO.: 1

COUNTY: Logan

TOTAL DEPTH: 4765'

ELEVATION: 3035 KB

COMMENCED: June 23, 1984

COMPLETED: June 30, 1984

CASING RECORD:

Surface: 6 jts. new 8 5/8" casing

Production: none

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Soil, clay, sand	0	270	Ran 6 jts. new 8 5/8" surface casing set @ 260'. Cemented w/ 100 sx.
Shale	270	1060	
Sand, shale, lm. strks	1060	2572	common, 100 sx. 60/40 pozmix, 2%
Anhydrite	2572	2595	gel, 3% CaCl. Plug down @ 6:25 a.m.
Shale	2595	3499	June 23, 1984. Cement did circulate.
Shales and lime	3499	4381	
Lime	4381	4765	
			Plug w/ 190 sx. 50/50 pozmix, 6% gel, 3% CaCl, 1 sx. Celloflake as follows: 1st plug @ 2580 w/ 20 sx. 2nd plug @ 1600 w/ 100 sx 3rd plug @ 280 w/ 40 sx. 10 sx. and solid bridge @ 40' 10 sx. mousehole, 10 sx rathole. Plug down @ 5:30 a.m. June 30, 1984.

JUL 12 1984

State Geological Survey
WICHITA BRANCH

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

I, JOHN JAY DARRAH, JR. of MALLARD DRILLING CO., INC., certify
that this a true and correct copy of the log of the #1 Moeder