

7-12-33W

**CONFIDENTIAL**

*Confidential*

WORKOVER REPORT

#1-7 Carr  
NE/4, Sec. 7-12S-33W  
Scott County, Kansas

1-17-86 Move in double drum. Pull tubing and rods.

1-18-86 Perforate Pawnee 4444'-4450' with 2 shots per foot. Acidize with 500 gal. MCA. Swab back 79 bbls. of 83 bbls. load. Last pull, all oil. 1st 30 minute test: 9.86 barrels oil; 2nd 30 minute test: 9.28 barrels oil; 3rd 30 minute test: 9.28 barrels of oil. Swab 42.42 barrels of oil at 3850' from surface.

1-20-86 Weekend fillup 2250' oil. Acidize with 1500 gal. SGA. Treated through tubing because of oil in casing. Swab back 60 bbls. of 84 bbl. load. Swab back 93 bbls. Last pull, all oil. Swab test 30 minutes: 11.60 bbls. oil. Pull plug and perforate Altamont "C" at 4410'-4414' with 2 shots per foot. Set Baker plug at 4500'. Set bridge plug at 4430'. Shut down overnight.

1-21-86 3200' down to fluid. Swab down. Acidize with 250 gal. MCA. Swab back 66 bbls. of 82 bbl. load. 1st 30 minute swab test: 2.25 bbls. oil; 2nd 30 minute swab test: 4.67 bbls. oil. Shut down because of wind.

1-23-86 675' overnight fillup, (600' oil, 75' acid water). Swab 3.48 barrels of oil in 30 minutes, no water. Acidize with 1000 gal. SGA. 1st 30 minute test: 5.8 bbls. fluid (17% oil); 2nd 30 minute test: 3.48 bbls. (43% oil); 3rd 30 minute test: 2.32 bbls. (50% oil); 4th 30 minute test: 2.32 bbls. (44% oil).

1-23-86 500' fluid in hole (100% oil). Set packer at 4433'. Run tubing and rods. Put back on pump at 5:00 p.m.

1-24-86 Made 87 barrels of oil.

1-25-86 Made 93 barrels of oil.

1-26-86 Made 87 barrels of oil.

JUN 03 1987

KANSAS GEOLOGICAL SURVEY  
WICHITA BRANCH

1-21-1986  
State Geological Survey  
WICHITA BRANCH

RECEIVED  
STATE CORPORATION COMMISSION

FEB 2 1987

CONSERVATION DIVISION  
Wichita, Kansas

M