

Work over

State

County

Polk

Company

M-R

Well No.

1

Farm

Walters #1

Survey

C & O S.W.S.E

Block No.

Sec.

26

Twp.


12

Range

13W

Co-Ord.

Elev.



NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

| Date | Depth | |
|---------|---------|--|
| | TD 3590 | Acidized. Overcure |
| | | w/ 500 gal. A. - 10% |
| 4/10/70 | | dump. X ^{no} 33 bbls oil + 50% water |
| 4/11/70 | | dump. Sab. 49.80 bbls oil + 50% water |
| 4/12/70 | | dump. Sun. 49 bbls oil + 50% water |
| 4/13/70 | | digging up cable tools |

694963

| Date | Depth | |
|---------|-------|---|
| 4/14/70 | | to perforate Lansing Perf 16 holes 3520-24 2000 Acid, 15% 2nd. low. 11.77 lbs fluid per hour 10% water Max pressure 90 [#] on vacuum 10 min. Gravity 33° + well seal plug & perf. 3492.95 |
| 4/15/70 | | Seal plug 3510 Perf 16 holes 3493.97 2000 Acid, Max pressure 250 [#] on vacuum 5 min Swab 3 1/2 lbs w/ oil 30 minutes - 16 BOPH 33° Gravity |
| 9/14/70 | | |