

May, 1935.

✓
Eldorado #1 Walz, ✓
SE NE NW, 29-13S-11W,
Elevation 1809'

Pennsylvanian conglomerate 3315-3325'
3315-3320 Sandy white lime, with clay shales.
3320-3325 No sample.

Residuum 3325-3360'
3325-3360 Chert, white, somewhat weathered at top
but mainly milky rather than dead white.
Rare stained chert in top.

Ordovician Top 3360' Sub-sea, minus 1551'
Trenton 3360-3383'
3360-3383 Lime, white to yellow, coarsely crystalline.

Decorah 3383-3435'
3383-3385 Lime, with included sand.
3385-3390 Green shale, sand, and dense lime.
3390-3410 Green shale with sandy layers.
3410-3428 Green shale.
3428-3435 Green shale and rare coarse sand.

Arbuckle Top 3435' Penetration 3' Sub-sea, minus 1626'
3435-3438 Miller dolomite. White, finely crystalline.